

## Case Study – MSA Extra, Peterborough



In conjunction with Innsite UK Ltd, Cambs Glass was contracted for the supply of the curtain walling glazing Peterborough MSA Extra service station extension, located on the main traffic routes of the A14 & A1. Cambs Glass in house teams designed, manufactured and installed the Schuco FW50+ thermally broken pressure equalised glazing system, which was all fitted back to the builders work aperture and main supporting steelwork frame. The site remained operational for the duration of our works and our contracts team took special measures to ensure the

health and safety of all operates and customers as they continued their business as normal. As such Cambs Glass utilised specialist access equipment such as articulated booms and scissor lifts, all operated by our team of IPAF and PLASMA trained operators.

Due to the oversize glass units supplied, the contract called for the use of us of crane to assist with the installation, the contract lift supplied by Ainscrough Crane Hire included a full method statement and lift plan, and the use of a banksman, and lift supervisor. To complement the lift a specialist narrow glass vacuum lifter was supplied by the GGR group which allowed the glass units to be installed in the 500mm space between the scaffold and the steelwork.

Throughout our works the hungry customers were able to have unrestricted access to all the service station facilities.

