

## Case Study – MSA Extra Cambridge



Following on for the successful partnership between Cambs Glass Ltd and Innsite UK Ltd at the MSA Extra service station at Peterborough. Cambs Glass was once again contracted for the supply of the curtain wall glazing elements at MSA Extra, Cambridge. Cambs glass in house teams designed, manufactured and installed the Schueco FW 50+ thermally broken, pressure equalised glazing system and glass units, which were all fitted back to the builders work aperture and main supporting steelwork frame. Like the Peterborough development the site reminded operational for the duration of the works and our contracts team took special measure to ensure the health and safety of all operatives and customers as they continued their business as normal. As such Cambs Glass utilised specialist access equipment such as articulated booms and scissor lifts, all operated by our team of IPAF and PLASMA trained operatives.

Due to the oversize glass units manufactured by Cambs Glass in-house Glass Processing Department, the contract called for the use of a crane to assist with the installation. The contract lift supplied by Ainscrough Crane hire included a full method statement and lifting plan, plus the use of a banksman and lift supervisor. To complement the lift a specialist narrow glass vacuum lifter was supplied by the GGR Group which allowed the glass units to be installed in the 500mm gap between the scaffold and steelwork.

